

- 4. PIPE T&P VALVE TO WITHIN 6" OF DRAIN WITH NO SHUTOFF VALVES OR RESTRICTION IN THE LINE; OR PER LOCAL CODE REQUIREMENTS. CONDENSATE
- DRAIN LINE WITH NEUTRALIZER PIPED TO FLOOR DRAIN NOT SHOWN. DUPLICATE REQUIRED PIPING FOR HEATER(S) AND STORAGE TANK(S).
- 5. IF PERMITTED BY LOCAL CODES, A CHECK VALVE MAY BE USED IN PLACE OF A BACKFLOW PREVENTER.
- 6. REFER TO INSTALLATION CHAPTER OF OMM-0175 FOR AIR, GAS, AND CONDENSATE CONNECTIONS.
- 7. ALL (\*) COMPONENTS ARE OPTIONAL FOR INSTALLATION UNLESS OTHERWISE STATED PER LOCAL CODE REQUIREMENTS.
- 8. THE FOLLOWING COMPONENTS SHALL BE FIELD SOURCED: CHECK VALVES, STRAINERS, BALL VALVES, BALANCING VALVES, PUMPS, TEMPERATURE SENSORS, **EXPANSION TANK, BACKFLOW PREVENTER.**
- 9. BUILDING RECIRC PUMP DETERMINED BY PLUMBING ENGINEER AND MINIMUM FLOW VARIES BY DIGITEMP MODEL.
- 10. HEATERS SHOULD BE PIPED REVERSE RETURN AS SHOWN OR BALANCING DEVICES ON THE OUTLETS OF THE HEATERS SHOULD BE EMPLOYED.
- 11. MOTORIZED/SEQUENCING VALVE WIRED INTO EACH UNIT'S INPUT/OUTPUT BOX CONNECT "AOUT" PER DRAWING SD-A-1357.
- 12. SEE CLEARANCE DIAGRAMS FOR APPROXIMATE INSTALLED FOOTPRINT WIDTH AND DEPTH.

<b>PAERCO</b>	Blauvelt, NY 10913		
INNOVATION – MULT UNIT, NO STORAGE TANK, SEQUENCING VALVES			
DRWN BY.	<b>DATE</b> 032025	DWG. NO: SD-A-1359	REV.